



Project Title: **WB TRINOMA**

Location: **L184 TRINOMA, EDSA CORNER NORTH AVENUE, QUEZON CITY**

Total Area: **50.42**


No. of Days to Complete: **35 working days**

ITEM	SCOPE OF WORKS	QTY.	UNIT	LABOR	Progress Percentage	Remarks
I	GENERAL REQUIREMENTS					
1	Mobilization and Demobilization					
	a. Deliveries & Pull out (Clearing of site, Hauling of debris, rubbish and Deep Cleaning)	1.00	lot			
	b. Board up	N/A	lot		N/A	
	c. Board down	1.00	lot			
	d. On Site Supervision " Project In-charge "	1.00	lot			
2	As-built plan (Signed and Sealed). Including Folder with Submittals, Construction Test Results and Certificates, Digital (Autocadd) & Signed and Sealed Scanned Copy.					
	a. Architectural					
	b. Electrical	5.00	sets			
	c. Mechanical					
	d. Fire Protection					
	e. Auxiliary Electronics					
	f. FDAS					
3	Temporary Facility	1.00	lot			
4	Permit and Documentation					
	a. Building Permit					
	b. Occupancy Permit	1.00	lot			
	c. BFP Permit					
	d. Etc. (CARI)					
II	ARCHITECTURAL WORKS					
	Cement plain finish NOT APPLICABLE		sqm			
a.	Floor Tile					
a.1						
	a. (FF-01) Selling / Fitting floor area : Supply and installation of 600mm X 600mm Gray/Cement Ceramic Floor Tiles (code M6664 "Floor Center"). 2mm or 3mm wide tile spacer with "Gray" ABC tile grout (Code F14).	34.79	sq.m.			
	b. (FF-02) Stock room floor area : Supply and installation of 300mm x 300mm MARIWASA ROMANA WHITE/ CAMPANA WHITE ceramic floor tiles in 2mm to 3mm wide tile spacer with "Gray" ABC tile grout (Code F15).	15.11	sq.m.			
	c. (FF-02) Stock room floor area : Supply and installation of 300mm x 300mm " STERLING GRAY " ceramic floor tiles, Brand : " APO VINYL ", Code : " SKU 001804 ", (From CW Homes), in 2mm to 3mm wide tile spacer with "Gray" ABC tile grout (Code F14).	N/A			N/A	
	d. (FF-02) Stock room floor area : Supply and installation of 2" Thk. (Verify Actual) Concrete topping in " Epoxy floor paint Finish " Two (2) Coat's.	N/A			N/A	
	e. Entrance Portal and Stock room Entrance : Supply and installation of 4mm Thk. Stainless Steel Tile Termination .	3.85	l.m			
b.	Wall					
b.1						
	a. Perimeter Wall : Supply and installation of 1/2 Thk. Gypsum board "Single Wall" on 64mm Vertical and Horizontal Metal Framing @ 600mm o.c, 5400mm (H) (See plan for details and location)	132.78	sq.m.			
	b. Partition Wall : Supply and installation of 1/2 Thk. Gypsum board "Double Wall" on 64mm Vertical and Horizontal Metal Framing @ 600mm o.c, 5400mm (H) (See plan for details and location) Verify on actual.	28.45	sq.m.			
	c. Entrance False Column : Supply and installation of 3/4 Thk. MDF BOARD on 64mm Vertical and Horizontal Metal Framing @ 3013mm (H) (See plan for details, location & Reference)	N/A	sq.m.		N/A	
	d. Wall Module Nailer : Supply and installation of 3/4 Thk. 200mm Wide Marine ply board @ 2600mm (H) , including Door Jamb Nailers, Column Cladding etc. (See plan for details and location)	16.64	sq.m.			

	e. Graphics Wall : Supply and installation of 1/2 Thk. Gypsum board on 64mm Vertical and Horizontal Metal Framing @ 3013mm (H). (See plan for details and location)	N/A	sq.m.		N/A	
	f. Column Cladding : Supply and installation of 1/2 Thk. Gypsum board on 64mm Vertical and Horizontal Metal Framing @ 3013mm (H). (See plan for details and location)	N/A	sq.m.		N/A	
b.2	Glass and Glazing					
	a. (GL-1) Front Show Window : Supply and installation of 2400mm (H) x Verify Actual (W) 12mm Thk. Frameless Clear Tempered glass panel on aluminum u-channel with rubber block with "Clear" Prosil silicone sealant on gaps. (Verify actual dimensions on site) Accredited Contractor : SYZ BUILDERS "Contact number : 09190020522 Mr.Chad Duran"	N/A	pcs		N/A	
	b. (GL-1) Front Show Window : Supply and installation of 3013mm (H) x 1746mm (W) 12mm Thk. Frameless Clear Tempered glass panel on aluminum u-channel with rubber block with "Clear" Prosil silicone sealant on gaps. (Verify actual dimensions on site)	N/A	pcs		N/A	
c.	Ceiling					
c.1						
	a. Ceiling Light : Supply and installation of Suspended C-Channel for Lighting Fixture Mounting including hangers and support etc. @ Selling Area & Stock Room Area. (See Plan Detail)	56.15	l.m			
	b. Fitting Room Ceiling : Supply and installation of 1/2 Thk. Gypsum Board Fixed Ceiling on 64mm Metal Double Furring Framing.	1.14	sq.m.			
	c.Back Show Window : Supply and installation of 1/2 Thk. Gypsum Board Fixed Ceiling on 64mm Metal Double Furring Framing.	N/A	sq.m.		N/A	
	d. Show Window Drop Ceiling : Supply and installation of 12mm Thk. Gypsum Board Fixed Ceiling on 64mm Metal Double Furring Framing. (See plan detail and location)	N/A	sq.m.		N/A	
	e. Store Signage Band / Portal : Supply and installation of 18mm Thk. MDF Board on 64mm Metal Double Furring Framing. (See plan detail and location)	24.48	sq.m.			
	f. General Ceiling : Supply and installation of 9mm Thk. Gypsum Board Fixed Ceiling with 50mm Shadow line on 64mm Metal Double Furring Framing including support hanger and accessories.	N/A	sq.m.		N/A	
d.	Doors					
	a. Main Door : Supply and installation of (2) 2400mm (H) X 900mm (W) 12mm Thk. Frameless clear tempered "Double Swing Glass Door" with (H-handle and Patch fittings). (See plan for details)	N/A	set		N/A	
	b. Stock Room Door : Supply and installation of (1) 2400mm (H) X 750mm (W) Pre-Fab "Single Swing Metal Door" with (fittings and accessories). (See plan for details)	OSM	set		OSM	OSM
	c. Fitting Room Door : Supply and installation of (1) 1920mm (H) X 750mm (W) Pre-Fab "Single Swing Metal Door" with (fittings and accessories). (See plan for details)	OSM	set		OSM	OSM
e.	Finishes					
e.1	Wall					
	a. (PT-01) General Walls : TITAN SUPER GREY "TINGE OF GRAY" SEMI GLOSS PAINT for General walls and fitting room wall, back show window walls (including wall preparation primer and "two coat finishing" etc.)	71.89	sq.m.			
	b. (PT-02) Stock Room Wall : 2 coats "Boysen 701" flat latex	N/A	sq.m.		N/A	
	c. (PT-03) Back Show Window Wall : Black Satin Paint Finish. (including wall preparation primer and "two coat finishing" etc.)	N/A	sq.m.		N/A	
e.2	Entrance Portal					
	a. (ACP-01) Portal & Signage Band : Supply and Installation of "ACP" Aluminum Composite Panel "SATIN BLACK". (See plan detail)	N/A	sq.m.		N/A	
	b. (ACP-02) Portal : Supply and Installation of "ACP" Aluminum Composite Panel "SATIN OFF WHITE" @ all Sides.	N/A	sq.m.		N/A	
	c. (ACP-01) Portal : Supply and Installation of "ACP" Aluminum Composite Panel "SILVER BRUSH / METALIC GRAY" @ all Sides.	24.48	sq.m.			
	d. Portal & Signage Band : Application of "Black Boysen Paint" on Perforated Metal sheed Substrate, including surface preparation etc.	N/A	sq.m.		N/A	
e.3	Ceiling					

	a. (CF-01) General Ceiling (Fixed/Open) : Selling area, Hanger, Support & Linear light mounting, Track light mounting C-Channel, Termination of perimeter dry wall to ceiling to slob soffit etc. as needed in Boysen Permacoat Latex Matte finish "Captain Nemo" Code : B714H307-A1 / 0542. (SEE RCP DETAILS)	111.13	sq.m.			
	BLACK SEMI GLOSS PAINT FOR WALLS (above left and right secondary walls)		sq.m.			
	b. (CF-02) Fitting Room : Painting of "Boysen" FLAT WHITE 701 latex paint "Fixed Ceiling"	1.14	sq.m.			
	RIBBED WALL (Back Counter) - By Metaline 25x25		sq.m.		not applicable/osm	
	ACP at exterior surface wall (white matte ACP)		lot			
	b. (CF-03) Stock Room : Bare no Paint	N/A	sq.m.		N/A	
	d. Show Window Drop Ceiling & Signage Band : Painting of Satin Black Paint Finish "Fixed Ceiling", including surface preparation etc.	N/A	sq.m.		N/A	
	Consumables	1.00	lot			
III	ELECTRICAL WORKS					
a.	Wiring and Conduits "EE Room to Lease Space"					
	a. Roughng-ins: (Panasonic or equal approved) IMC pipes and fittings for "Main Feeder Line to Lease Space" Stub out power supply. (Approx distance only verify on actual). (Use Unistrut Channel Support, Treaded Rod etc.)	N/A	l.m		N/A	
	Electrical Wire(philflex)					
	a. # 30.0 THHN	N/A	l.m		N/A	
b.	Wiring and Conduits					
1.						
	a. Roughng-ins: IMC pipes "MATSUSHITA/PANASONIC" and fittings for Lighting,POS / Audio (from speakers to source), Telco (from power supply to cashwrap counnter) Feeder line to Panel boards, (from entrance to cashwrap counter, video, DATA, CCTV walls, Led Graphics, Wall Signage, Air Curtain & Signage band Lighting provision. etc. as needed - VERIFY WITH PLANS (Use Metal Conduit Clip for Hanger Mounting & Unistrut Channel Support for wall, pullbox layout etc.). see photo for reference.					
	Elect. Wire and Cable (philflex)					
	a. # 3.5 THHN					
	b. # 5.5 THHN (as per plan)					
	c. # 8.0 THHN (as per plan)					
	d. # 14.0 THHN (N/A)					
	d. # 50.0 THHN (N/A)					
2.	Electrical Fixtures					
	a. Supply and installation of 2-gang wall mounted universal Convenience Outlet, brand: panasonic w/ Switch for (Lighted Graphics)	N/A	set		N/A	
	b. Supply and installation of Panasonic brand floor mounted 2 gang universal Convenience outlet w/ Switch for Lighted Graphics, Platform (See photo for reference)	1.00	pcs			
	c. Supply and installation of 2-gang wall mounted universal Convenience Outlet, brand: panasonic (Cash counter, Data Cabinet, Wall module, TV, emergency light Etc.)	24.00	set			
	d. Supply and installation of Panasonic brand floor mounted 2 gang universal Convenience outlet. (See photo for reference)	N/A	set		N/A	
						
	e. Supply and installation of Wall 3gang Switch, panasonic brand	2.00	sets			
	f. Supply and installation of Wall 2gang Switch, panasonic brand	2.00	sets			
	g. Supply and installation of Wall 1gang Switch, panasonic brand	2.00	sets			
	h. Supply and installation of Panasonic Timer Switch for LED Signage.	1.00	sets			
3.	OSM Lighting Fixtures / Modules & Shelvings "Installation only"					
	i. Installation of LED 3 WIRE TRACKLIGHT W/ PHILIPS 30W BRIDGELUX VERO 10 MODULE 830, PHILIPS LED DRIVER, 24D, BK	36.00	pcs		OSM	
	j. Installation of "1 meter" black track bar	12.00	pcs		OSM	
	k. Installation of 12w LED Circular panel Light	2.00	pcs		OSM	

	I. Installation of Exit Signage	2.00	pcs		OSM	
	m. Installation of Emergency Light	5.00	pcs		OSM	
	n. Installation of T5 LED Light "Day Light"	6.00	pcs		OSM	
	o. Installation of Ceiling Suspended Emergency Light	N/A	pc		n/a	
	p. Installation of Ceiling (Mounted / Suspended) Speaker w/ wiring.	2.00	pc		OSM	
	q. Installation of All Owner Supplied Items (As needed). Stock room shelvings, selling wall module, floor module, Cashier counter, Wall Mirror, Metal sheet panel for store Front/Signage band, Wall Light box Graphics, TV, Fitting room / stock room Door, Data Cabinet, Category signage etc. " See plan detail for reference"	1.00	lot		OSM	
4 .	Panel Board					
	Panel board assembly bolt-on industrial type CB. "Brand : ABB, SCHNEIDER, SQUARE D" (See Electrical Plan)	1.00	set			
	"LPPB"					
	a. Main CB : MCCB 40AT/50AF, 3P, 4000v, 30KAIC	1.00	sets			
	b. Branch : MCB 20AT/50AF , 1P	8.00	sets			
	c. Branch : MCB 30AT/50AF , 1P	N/A	sets		N/A	
	d. Branch : MCB 40AT/50AF , 1P	N/A	sets		N/A	
	e. Branch : MCB 50AT/50AF , 1P	N/A	sets		N/A	
	f. Branch : MCB BLANK no braker "For Spare"	N/A	sets		N/A	
	g. Electrical panel board "Nema 1" enclosure	1.00	set			
	Panel board assembly bolt-on industrial type CB. "Brand : ABB, SCHNEIDER, SQUARE D" (See Electrical Plan)					
	"PB2"	N/A			N/A	
	a. Main CB : MCCB 40AT/50AF, 3P, 390v, 25KAIC	N/A	sets		N/A	
	b. Branch : MCB 20AT/50AF , 1P	N/A	sets		N/A	
	c. Branch : MCB 30AT/50AF , 1P	N/A	sets		N/A	
	d. Branch : MCB 40AT/50AF , 1P	N/A	sets		N/A	
	e. Branch : MCB 50AT/50AF , 1P	N/A	sets		N/A	
	f. Branch : MCB BLANK no braker "For Spare"	N/A	sets		N/A	
	g. Electrical panel board "Nema 1" enclosure	N/A	set		N/A	
	Consumables	1.00	lot			
IV	FIRE DETECTION AND ALARM SYSTEM WORKS					
1 .	Supply and installation of Smoke detector including its Wires, Pipe, fittings and accessories. (See plans detail and location) "Accredited Contractor : . Mobile number : ""	3.00	units			
	Consumables	1.00	lot			
V	MECHANICAL WORKS					
1 .	Airconditioning					
	b. Supply and Installation of 300mm Diameter Circular Air Diffuser	6	pcs			
	b. Supply and Installation of 600mm x 100mm Supply Air Diffuser	1	pc			
	b. Supply and Installation of 500mm x 400mm Return Air Grille	1	pc			
	b. Supply and Installation of 250mm x 200mm Air Duct, Plenum Mounted & 200x200 FAG.	2	sets			
	e. Supply and installation : Retro Fitting of G.I Air Ducts & Fresh Air duct, including hangers, Support & accessories (See plan details and location)	1	lot			
	f. Supply and installation of 4TR ceiling concealed type FCU "CARRIER" Brand Model : 40LM 050, including Pipes, hanger & support, Vibration isolator, Spring damper etc. (See plan detail)	1	Unit			
	Consumables	1	lot			
VI	FIRE PROTECTION WORKS					
1 .	Sprinkler head "Accredited Contractor : n/a . Mobile number : "n/a"					
	a. Relocation of "Pendent Type" Sprinkler head.	N/A	set		N/A	
	b. Relocation of "Up right" Sprinkler head.	N/A	set		N/A	
	c. Supply and Installation of new "Pendent type" Sprinkler head.	1.00	set			
	d. Supply and Installation of new "Up right" Sprinkler head.	4.00	set			
	Consumables	1.00	lot			
VII	SPECIAL FABRICATION WORKS					
1 .	Carpentry					
	a. Supply and Installation of 3/4 Thk. MDF Board box for Suspended Speaker, Painted finish "Captain Nemo"	2.00	pcs			

	b. Supply and Installation of 3/4 Thk. MDF Board box for Suspended Pilot Light. (Same detail with Speaker box)	1.00	pc			
2 .	Pest Control					
	a. Supply and installation of 1'x1' Wire mesh ceiling perimeter pest control. (use existing provide cost for retro fitting etc.)	N/A	lot		N/A	
3 .	Hardwares					
	a. Supply and Installation of Home aide Coat hook SUS 304, SKU : 3150230809835 or equal. "Fitting Room"	1.00	pcs			
						
	b. Supply and installation of "YALE series 4000" Heavy duty Door closer for stock room door.	1.00	wd			
						
	c. Supply Installation of Maintenance Hand Hole Column cladding. (See plan detail 5 A-5)	N/A	pcs		N/A	
	d. Supply Installation of 600mm X 600mm Maintenance Man Hole. (See plan detail)	N/A	pc		N/A	
4 .	Roll - Up Door					
	a. Supply and Installation of 3212mm (L) x 3400mm (H) Automatic Motorized Polycarbonate Roll-up Door	1.00	Unit			
5 .	Ramp					
	a. Supply and Installation of Steel metal ramp, with anti rust paint. (See plan detail)	N/A	set		N/A	
6 .	Metal Catwalk					
	a. Supply and Installation of Steel metal catwalk 1200x400mm, with anti rust paint, including hanger and support. Etc. (See plan detail)	1.00	set			
7 .	Blade Signage					
	a. Supply and Installation of Blade Signage frame and bracket etc. (See plan detail)	1.00	set	additive-deductive		
	Consumables	1.00	lot			
VIII TESTING AND COMMISSIONING						
	a. Electrical "Megger test"					
	b. Full load test					
	c. Light Test					
	d. Air balancing					
	e. Functionality Test (FDAS)					
	f. Pressure Test "Sprinkler"	1.00	lot			
	g. Tempered glass Certificate (N/A)					
	h. Fire Proofing Application Certificate					
	i. Aircon Chemical flushing					
	ETC.					
IX ITEMS NOT SPECIFIED IN THE BID FORM						
1 .						
	a. perimeter wiremesh	48.32	sqm			
	b. floor topping	50.42	sqm			
	c.					
	d.					